

---

## Pohokura South-01B Flow Tests Near Completion

**O**perator of the Pohokura South-01B onshore appraisal well, Shell Todd Oil Services (STOS), said 7 day and 14-day tests were carried out in June and early July.

After the 7-day test, the well was closed in on June 15th for a 2-day pressure build-up test,

followed by retrieval of the downhole temperature and pressure gauges.

The two week test began on June 19th. The well is appraising gas and condensate flows from the southern end of the offshore Pohokura field (in PEP 38459) through the 5032 m (along-hole) well which was drilled out to about 2.6 km off the coast late last year. ■